

Govt. of West Bengal

O/o the Chief Medical Officer of Health, South 24 Parganas

M.R Bangur Hospital. Building, 2nd floor, Tollyguge, Kolkata

☎: (033) 2473-1039 ; Fax: (033) 2473 0294:

E-mail: cmoh_s24@wbhealth.gov.in

For Details Log On: www.wbtender.gov.in

Memo. No. CMOH(SPG)/ 365

Dated.- 10.01.23

E- TENDER NOTICE NO. – 12/ NHM of 2022-23 (Civil & Electrical work) (2nd call)

1. Chief Medical Officer of Health & Secretary District Health & Family Welfare Samity, South 24 Parganas at M.R Bangur Hospital, 2nd floor, Kolkata-33, South 24 Parganas, invites e-tender from the intending experienced bonafide eligible resourceful outsiders and working contractors/agencies having experience in relevant nature and magnitude of the constructional work mentioned as noted in ANNEXURE-I(Enclosed).
2. The accepting authority does not bind him –self to accept the lowest bidder and reserves the right to reject any or all of tenders received, without assigning any reasons. He further reserves the right of splitting up any contract and distributing the same to more than one bidder.
 - a. **This is an e-procurement tender and also a two bid tender. First bid should contain document of earnest money & technical documents (i.e. trade license, pan card, credential etc.)and second bid should contain the financial offer to be submitted online.**
3. **Contractors /agencies are requested to observe the required credential. If any agency found submitted bid for the specific serial with below credential or false credential or any false paper the earnest money will be forfeited.**
4. The intending bidders should submit tenders within specified time along with **scanned copies of original documents (scan of Xerox copy of any documents is not allowed)** –
 - a. Trade License (Civil) (valid for current period 2022-2023),
 - b. Trade License (Electrical) (valid for current period 2022-2023),
 - c. G.S.T Registration No. With current return. 2022-23
 - d. Professional Tax Enrolment Certificate with current year payment challan/return,
 - e. Pan Card.
 - f. I.T Return for Assessment years 2021-22 & 2022-2023
 - g. Separate Agreement (Notarized) need to be executed by agency with Civil & Electrical Engineer (at least a Diploma Certificate Holder).
 - h. If the Agency /Bidder /Firm/Company is not an Electrical License holder,he/she should submit agreement paper executed in between the bidder & Electrical license holder and such Agreement should be at least be in the form of 1st Class Judicial Magistrate.
 - i. **Credentials:** Completion/ payment certificate with relevant work order of Govt. offices/ Govt. undertakings/ local bodies of **similar nature of job** as noted in annexure-I (enclosed) Credentials under sub-contract is not valid. The intending bidder should produce credential of similar nature of structural works of a completed single work having minimum value of 40% (Forty per cent) of the estimated amount put to tender during 03 (THREE) years prior to the date of the issue of the e-Tender notice.
 - j. The Agency /Bidder /Firm/Company must arrange visit of their Civil and Electrical Engineer (atleast a diploma holder) during the execution of work and may be summoned for sharing necessary details if felt required by the tender inviting authority.
 - k. In case of a partnership firm; it must be registered under any law.
 - l. In case of a partnership firm/ co-operative institution there should be clearly mentioned the authorized person who carry on the business in favor of the institution in form of deed/agreement / resolution if applicable.
5. ***State Team & district team will make periodical onsite visit to review the progress of the work and check the quality of work being implemented.***
6. The intending bidders shall have to furnish original certificates of all documents with execution of similar works of requisite magnitude as and when demanded by the tendering authority.

7. The Tender Inviting Committee has reserved the rights to accept/cancel any/all of the Tender at any phase of the process without further reference
8. The bidders notice and details schedule of works may be obtained from the **website:www.wbtender.gov.in**
9. No price escalation will be allowed in any circumstances.

10. Date and Time Schedule of Tender:-

SL NO.	Particulars	Date & Time
1	Date of publishing N.I.T & other documents online	13/01/2023 05:00 P.M
2	Online documents download starting date	13/01/2023 05:00 P.M
3	Online documents download ending date	20/01/2023 05:00 P.M
4	Online submission start date	13/01/2023 05:00 P.M
5	Pre-bid meeting to be held at office of CMOH	17/01/2023 02.00 P.M
6	Dates for submission of earnest money deposited online	As per Memorandum memo No.- 3975-F(Y), dtd.-28 th July 2016
7	Online bid submission closing date	20/01/2023 05:00 P.M
8	Online bid opening date for technical proposals	24/01/2023 02:00 P.M
9	Date of online uploading list for technically qualified bidders	To be notified later
10	Date of online opening of financial proposal	To be notified later

11. The bidder should quote his /their rates in figures and words on the basis of percentage above, below or at par with the schedule of rates attached with the tender form online.

12. **A) As per Govt. Order No. 4608 - F(Y) Dated 18/07/18, to ensure the quality and prior execution of the work in public interest, the Governor is pleased to decide that Additional Performance Security @10% of the tendered amount shall be obtained from the successful bidder if the accepted bid value is 80% or less of the estimate put to tender.**

B) The additional Performance Security shall be submitted in the form of Bank Guarantee from any Scheduled Bank before issuance of the Work Order. If the bidder fails to submit the Additional Performance Security within seven working days from the date of issuance of Letter of Acceptance, his earnest money will be forfeited and other necessary actions as per NIT like blacklisting of the contractor, etc. may be taken. The Bank Guarantee shall have to be valid up to end of the Contract Period and shall be renewed accordingly, if required.

C) The Bank Guarantee shall be returned immediately on successful completion of the Contract. If the bidder fails to complete the work successfully, the Additional Performance Security shall be forfeited at any time during the pendency of the contract period after serving proper notice to the contractor. Necessary provisions regarding deduction of security deposit from the progressive bills of the contractor as per relevant clauses of the contract shall in no way be altered/ affected by provision of this Additional Performance Security.

13. **A) Cost of tender paper:** Not required.

B) Earnest money: Earnest money [as indicated in the corresponding column of the work in the annexed sheet that 2% of A.P.T (in Rs.) should be deposited by the bidder [except Micro and Small Enterprise (MSEs) as defined in MSE Procurement policy issued by Department of Micro, Small and Medium Enterprise (MSME)] through e-procurement portal as per Memorandum, memo. 3975-F(Y), dtd. - 28. 07.2016.

C) Performance Security will be deposited/deducted from bill at the prevailed rate as per the order of the Finance Department, Govt. of West Bengal vide its Memo No. 201-F(Y) dated 18.01.2021.

14. The successful bidder/s should execute an agreement with **District Health & Family Welfare Samity, South 24 Parganas** within ten days from the date of acceptance of the tender, failing which the tender be liable to be rejected.
15. Bidder /s shall be bound to execute any excess and supplementary works as may be ordered by the TIA at the rate of prevailing schedule of PWD/PW(R) D, GOVT. OF W.B at the time of tender submission.
16. Due to work at Hospital the Contractors/Agencies will be responsible for work at emergency basis and urgently finishing the work
17. All tools and plants and implements required for the construction of the work, will have to be supplied by the contractor at his/their own cost.
18. The applications of the bidder, who could not complete the works entrusted to them in past to the full satisfaction of this **District Health & Family Welfare Samity , South 24 Parganas** , will not be considered.
19. Security Deposit, Labour Welfare Cess, T.D.S on Income Tax and G.S.T. will be deducted from the bills as per Govt. Rules. EMD/ Security Deposit will be released as per Govt. rules (vide memo.- 5696-F(Y), dtd.-01st October 2019 read with Memorandum Vide memo No. – 201- F(Y), dtd.- 18.01.2021).
20. Copy of this NIT along with tender document may be obtained from the website:www.wbtender.gov.in
21. Any eligible bidder will be assigned job anywhere within the district as per the decision of Department/Tender Committee.
22. The Tender Committee reserves the rights to accept/cancel any/all of the Tenders at any phase of the process without further reference. If in any Bid, more than 01 nos. of LI bidder is found suitable after opening of financial bid, the Tender committee/ authority may conduct Draw of Lots for further decision.
23. The payment of the agency will be released after issuance of work-done satisfactory received from the concerned authority and certifying by the Engineering Cell.
24. State inspection team from Swasthya Bhawan will make periodical on site visits to review the progress of work and check the quality of work being implemented .no payments will be made until the clearance on the quality of the work has been permitted from higher authority..
24. All intended bidders are requested to keep close vigil on Website & on Office Board for any subsequent notice.

Secretary

District Health & Family Welfare Samity
South 24 Pgs & CMOH, South 24 Parganas

For Details Log On : www.wbtender.gov.in

Memo. No. CMOH(SPG)/ 365/1(19)

Dated : 10.01.23

Copy forwarded for information & with a request to display the Tender Notice in the notice board to -----

1. The Sabhadhipati, South 24 Parganas, Zilla Parisad
2. The Executive Vice Chairman, District Health & Family Welfare Samity, South 24 Parganas & The District Magistrate, South 24 Parganas. You are requested to send a representative at the time of opening of Bid.
3. The Executive Director State Health & Family Welfare Samity, Swasthya Bhawan
4. The Mission Director, NHM, Swasthya Bhawan
5. The Senior Accounts Officer, NHM, Swasthya Bhawan.
6. The Engineer in Charge , NHM, Swasthya Bhawan
7. The Progrmme Officer-I, NHM Swastha Bhawan
8. The Dy C.M.O.H-1, CMOH Office, South 24 Parganas
9. The Accounts Officer, CMOH Office, South 24 Parganas
10. The ACMOH Baruipur /Sadar/Canning Block ,South 24 Parganas
- 11-15. The BMOH (ALL) Block ,South 24 Parganas
16. The Assistant Engineer, SPMU, NHM, Swasthya Bhawan, Kol.
17. CA to District Magistrate, South 24 Pgs.
18. CA to ADM (D), South 24 Pgs.
19. Office files.

Secretary

District Health & Family Welfare Samity
South 24 Pgs & CMOH, South 24 Parganas

E- TENDER NOTICE NO.- 12 / NHM of 2022-23 (Civil & Electrical work)(2nd call)**Annexure-I**

SL NO	NAME OF BLOCK	NAME OF WORK	A.P.T (In Rs.)	EARNEST MONEY (In Rs.)(2.0% of A.P.T)	COMPLETION OF TIME
1	Sonarpur	Repair & renovation work for establishment of Ayush HWC AT SONARPUR SAD under sonarpur block,south 24 pgs. (The tendered work has to be carried out as per the Estimated Amount. GST amount will be 12% and no extra cost such as riverine cost will be given for the said work in any circumstances.)	6,64,412.00	13,288.00/- (As per Memorandum memo No.- 3975-F(Y), dtd.-28 th July 2016)	30 days
2	BISHNUPUR-I	Repair & renovation work for establishment of Ayush HWC AT East Bishnupur SHD under Bishnupur-I block, south 24 pgs. (The tendered work has to be carried out as per the Estimated Amount. GST amount will be 12% and no extra cost such as riverine cost will be given for the said work in any circumstances.)	1,45,143.00	2,903.00/- (As per Memorandum memo No.- 3975-F(Y), dtd.-28 th July 2016)	15 days

Secretary

District Health & Family Welfare Samity
South 24 Pgs & CMOH, South 24 Parganas

Repair & Renovation for Establishment of Ayush HWC at Sonarpur SAD under Sonarpur block South 24 Parganas

Sl no	Description	Nos	L	W	H	QUT.	UNIT	RATE	AMOUNT
	item no-10 ,page-11								
1	Stripping off worn out plaster and raking out joints of walls, celings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed.	1	17.50	-	1.50	26.25			
		1	6.50	1.20		7.80			
		1	4.50	4.18		18.79			
		1	3.00	2.80		8.40			
		1	3.50	2.90		10.15			
						71.39	sq.m	19.00	1356.36
	item no-16 ,page-16, 3rd corrigenda & Addenda								
2	125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor	1	1.8	-	3	5.4			
						5.4	Sqm	723.00	3904.20
	item no-33.,page-12, 3rd corrigenda								
3	Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. (pakur variety)								
		1	11.5	7.5	0.25	21.56			
		1	5	3.5	0.125	2.19			
						23.75	Cu.M.	6384.39	151629.26
	item no-36 ,page-42								
4	Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor)a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge								
		1	8.2		7.6	62.32			
		1	5	3.2		16			
						78.32	sqm	335	26237.2
	page-01, sl.-01, 9th corrigenda								

5	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction.) Tor steel/Mild Steel. SAIL/TATA/RINL				1*1.0%*7.85*23.75	1.864	M.T	60580	112943.84
item no-4 ,page-22, 3rd corrigenda									
6	Artificial stone in floor, dado, staircase etc with cement concrete (1:2:4) with stone chips, laid in panels as directed with toppingng of concrete surface and application of cement slurry before flooring works using cement @ 1.75 kg/sq.m all complete including all materials and labour.In ground floor. 3 mm. thick topping (High polishing grinding on this item is not permitted with ordinary cement). Using grey cement(iii) 35 mm. thick	1	3	4.2		12.6			
		1	3.5	2		7			
item no-15, Page-192									
7	Neat cement punning about 1.5mm thick in wall, dado, window sill, floor etc. NOTE:Cement 0.152 cu.m per100 sq.m.	1	3	4.2		12.6			
		1	2.6	1.2		3.12			
		1	2.6	1.2		3.12			
		1	2.5	1.2		3			
		1	1.8	1.2		2.16			
		1	3	3.35		10.05			
		1	7.5	1.2		9			
		1	3.5	2		7			
						50.05	sq.m	34.00	1701.7
item no-1, Page-192									
8	Labour for Chipping of concrete surface before taking up Plastering work.	1	3.35		3.00	10.05			
		2	1.20		3.00	7.20			
		2	1.80		3.00	10.80			
		2	1.20		3.00	7.20			
		2	2.25		3.00	13.50			
						48.75	sq.m	21.00	1023.75
Page no :47 Item No:3									
9	Supplying and laying Polythene Sheet (150gm / sq.m.) over damp proof course or below flooring or roof terracing or in foundation or in foundation trenches.								
		2	3	2		12			

	2	2	1		4			
	4	7.5		0.15	4.5			
	4	8.2		0.15	4.92			
	3	0.9		1.2	3.24			
	1	0.9		1.2	1.08			
	1	0.7		0.6	0.42			
	1	0.6		1.2	0.72			
	1	8.2		7.6	62.32			
	1	5	3.2		16			
					109.2	sqm	24	2620.8
	item no-10 ,page-91, 3rd corrigenda							
10	(a) M.S or W.I Ornametal grill of approved design joints contluously welded with M.S, W.I flats and bars of Windows, railing etc. Fitted and fixed with necessary screws and lugs in ground floor.(Add extra @ 1% for each addl. Floor upto 4th floor and @ 1.25% for each addl. floors above 4th floor) (i) Grill weighing above 10kg per sq.m and up to 16Kg./sq.mtr.							
	1	1.2		2.1	2.52			
	1	1.5		1.2	1.8			
					4.32			
					0.52	Qntl	9,888	5125.94
	item no-01 Page 49, 3rd corrigenda							
11	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/ staging where necessary (ground floor). [Excluding cost of chipping over concrete surface] (i) with 1:6 cement mortar (b)15 mm Thick Plaster							
	1	3.00		3.60	10.80			
	1	2.00		3.60	7.20			
	1	3.00		3.00	9.00			
	1	2.00		3.00	6.00			
	1	2.00		2.40	4.80			
	1	3.00		2.40	7.20			
					45.00	Sqm	151.00	6795.00
	item no-1, Page 50, 3rd corrigenda							

12	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/ staging where necessary (ground floor). [Excluding cost of chipping over concrete surface](i) with 1:4 cement mortar (c)10 mm Thick Plaster							
		1	6.50	1.20		7.80		
		1	2.25	1.20		2.70		
						10.50	Sqm	133.00
	item no-1,Page 49 3rd corrigenda							
13	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/ staging where necessary (ground floor). [Excluding cost of chipping over concrete surface] (i) with 1:6 cement mortar (a)20 mm thick plaster							
	out side wall	1	8.20		3.6	29.52		
		1	7.55		3.6	27.18		
		1	8.20		0.6	4.92		
		1	7.55		0.6	4.53		
						66.15	Sqm	175.00
	Item no-35,Page 65							11576.25

14	Supplying, fitting & fixing 1st quality Ceramic tiles in walls and floors to match with the existing work & 4 nos. of key stones (10mm) fixed with araldite at the back of each tile & finishing the joints with white cement mixed with colouring oxide if required to match the colour of tiles including roughening of concrete surface, if necessary or by synthetic adhesive & grout materials etc(B) Wall With Sand Cement Mortar (1:3) 15 mm thick & 2 mm thick cement slurry at back side of tiles using cement @ 2.91 Kg/Sq.m & joint filling using white cement slurry @ 0.20kg/Sq.m. (a) Area of each tile upto 0.09 Sq.m (ii) Other than Coloured decorative including white 2. Add extra for each addl. floor over the rate for item 35 & 36 of subhead A. (i) upto 4 th floor-Rs 5/ Sq.m								
	toilet ground floor, floor item no-10 page no-196	4	2.2		2.1	18.48	Sqm.	704.00	13009.92
15	Acrylic Distemper to interior wall, ceiling with a coat of solvent based interior grade acrylic primer (as per manufacturer's specification) including cleaning and smoothing of surface. Two Coats								
		4	3.00		3.20	38.40			
		1	2.00		8.50	17.00			
		1	6.35		3.00	19.05			
						74.45	Sqm	70.00	5211.5
		1	6.50	1.20		7.80			
		1	3.00	4.18		12.53			
		1	3.00	3.35		10.05			
		1	1.80	1.20		2.16			
		2	2.53	1.20		6.06			
		1	2.25	1.20		2.70			
						41.30	Sqm	70.00	2890.65
	item no-9 page no-196b								
16	Dry Distemparing to interior walls or ceiling including cleaning, washing, smoothing surface(b) Two coat								
		4	3.00		3.20	38.40			
		1	2.00		8.50	17.00			
		2	3.00		3.00	18.00			
		2	4.18		3.00	25.05			
						98.45	Sqm	49.00	4824.05


		1	6.50	1.20		7.80			
		1	3.00	4.18		12.53			
		1	3.00	3.35		10.05			
		1	1.80	1.20		2.16			
		2	2.53	1.20		6.06			
		1	2.25	1.20		2.70			
						41.30	Sqm	49.00	2023.455
	item no-7 page no-195b								
17	Applying Interior grade Acrylic Primer of approved quality and brand on plastered or concrete surface old or new surface to receive Distemper/ Acrylic emulsion paint including scraping and preparing the surface thoroughly, complete as per manufacturer's specification and as per direction of the EIC. (In Ground Floor)(b) Two Coats) Water based Interior grade Acrylic Primer								
	out side wall	2	8.20		3.6	59.04			
		2	7.55		3.6	54.36			
	parapate wall	2	8.20		0.9	14.76			
		2	7.55		0.9	13.59			
						141.75	Sqm	44.20	6265.35
	item no-4 page no-201								
18	Applying Acrylic Emulsion Paint of approved make and brand on walls and ceiling including sand papering in intermediate coats including putty (to be done under specific instruction of Superintending Engineer) : (Two coats) i) Standard Quality								
	out side wall	2	8.20		3.6	59.04			
		2	7.55		3.6	54.36			
	parapate wall	2	8.20		0.9	14.76			
		2	7.55		0.9	13.59			
						141.75	Sqm	62.00	8788.5
	item no-1/ f page no-114								
19	Wood work in door and window frame fitted and fixed in position complete including a protective coat of painting at the contact surface of the frame excluding cost of concrete, Iron Butt Hinges and M.S clamps. (The quantum should be corrected upto three decimals). (f) Sishu, Gamar, Champ, Badam, Bhola, Mogra, Hallak.	3	6.4	0.075	0.100	0.14	Cum.	76096.00	10957.82


item no- (1) (iii) (b) page no-117								
20	Panel shutters of door and windows, as per design (each panel consisting of single plank without joint), including fitting and fixing the same in position but excluding the cost of hinge and other fittings.(iii) 35 mm thick shutters with 19mm thick panel (b) Sishu, Gamar, Champ, Badam, Bhola, Mogra, Hallak.	1	1.0	-	2.1	2.10		
		1	0.9	-	2.1	1.89		
		1	1.2	-	1.2	1.44		
						5.43	Sqm.	2948.00 16007.64
item no-4 /b,page no-140								
21	Supplying, fitting and fixing M.S clamps for door and window frame made of flat bent bar, end bifurcated with necessary screws etc. by cement (1:2:4) as per direction. (Cost of concrete will paid separately) (b) 40mm X 6mm X 200mm length	8	-	-	-	8.00	Each	25.00 200
Item no-5/ vii,page no-140								
22	Iron butt hinges.... (vii) 100mm. X 58mm. X 1.90mm.	8	-	-	-	8.00	Each	47.00 376
Item no- 28/i Page 145								
23	Anodised aluminium Aldrop/ Sliding bolts approved quality manufactured from extruded section conforming to I.S specification (I.S 2681/66) and fitted and fixed complete. (i) 250 mm X 16 mm dia. Bolt.	4	-	-	-	4.00	Each	233.00 932
item no-10/c Page 138								
24	Square or hexagonal square mesh netting made with 18 BWG galvanized wire fitted and fixed complete as per design including local sal wood battens of size 37.5mm X 25mm. C) 37.5mm mesh	4	1.8	-	1.4	10.1	Sqm	373.00 3759.84
item no-1/b, page no-200								
25	(b) Priming one coat on timber or plastered surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc. (i) For Door & Window	5	1.8	-	1.4	12.6	Sqm	38.00 478.80
item no-1/a, page no-200								
26	(a) Priming one coat on steel or metal surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc.	1	15.5	-	1.4	21.7	Sqm	29.00 629.3


item no- 2 A/a/ii page no-200									
27	(A) Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary. (a) On timber or plastered surface with super gloss (hi-gloss) (iv) two coats (white in shade) (i) For Door & Window	5	1.8	-	1.4	12.6	Sqm	78.00	982.8
item no- 2 A/b/ii page no-200									
28	b) On steel or other metal surface	2	12.3	-	1.2	29.52			
		2	1	-	2.1	4.2			
						33.72		77.00	2596.44
Item no-41a , page no-69									
29	Supplying and laying true to line and level vitrified tiles of approved brand (size not less than 600 mm X 600 mm X 10mm thick) in floor, skirting etc. set in 20 mm sand cement mortar (1:4) and 2 mm thick cement slurry back side of tiles using cement @ 2.91Kg./sqM or using polymerised adhesive (6 mm thick layer applied directly over finished artificial stone floor/Mosaic etc without any backing course) laid after application slurry using 1.75 Kg of cement per sqM below mortar only. Joints grouted with admixture of white cement and colouring pigment to match with colour of tiles / epoxy grout materials of approved make as directed and removal of wax coating of top surface of tiles with warm water and polishing the tiles using soft and dry cloth upto mirror finish complete including the cost of materials, labour and all other incidental charges complete true to the manufacturer's specification and direction of Engineer-in-Charge. (White cement, synthetic adhesive and grout material to be supplied by the contractor) (B) Light Colour								
	1st floor, room	1	3	4.2		12.60			
		1	3	3.1		9.30			
		1	4.5	1.2		5.40			
		1	3.00	2		6.00			
						Total		1276.00	42490.80
30	Logo & Marking (Non Schedule)	2					L.S	10000.00	20000.00
									475340.87

Cost of sanitary & plumbing work	47534.09
Cost of electrical work	47534.09
Total=	570409.04
Add 12% GST on Total amount	68449.09
Net Total=	638858.13
1% extra for labour welfare cess =	6388.58
Add 3% contingency=	19165.74
Grand Total:	664412.46
Say:	664412.00

Total RS. Six lakh Sixtyfour Thousand Four Hundred Twelve only /-.


Sub-Assistant Engineer
NHM, South 24pgs.


Assistant Engineer
NHM, South 24pgs.


CMOH
South 24pgs.

Repair & Renovation for Establishment of Ayush IIWC at East Bishnupur SHD under Bishnupur-I block South 24 Parganas

Sl no	Description	Nos	L	W	H	QUT.	UNIT	RATE	AMOUNT
	item no-10 ,page-11								
1	Stripping off worn out plaster and raking out joints of walls, celings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed.	1	17.50	-	1.50	26.25			
		1	6.50	1.20		7.80			
		1	4.50	4.18		18.79			
		1	3.00	2.80		8.40			
		1	3.50	2.90		10.15			
						71.39	sq.m	19.00	1356.36
	item no-4 ,page-22, 3rd corrigenda								
6	Artificial stone in floor, dado, staircase etc with cement concrete (1:2:4) with stone chips, laid in panels as directed with toppinging of concrete surface and application of cement slurry before flooring works using cement @ 1.75 kg/sq.m all complete including all materials and labour.In ground floor. 3 mm. thick topping (High polishing grinding on this item is not permitted with ordinary cement). Using grey cement(iii) 35 mm. thick	1	3	4.2		12.6			
		1	3.5	2		7			
						19.6	SQM	337	6605.2
	item no-15, Page-192								
7	Neat cement punning about 1.5mm thick in wall, dado, window sill, floor etc. NOTE:Cement 0.152 cu m per 100 sq.m.	1	3	4.2		12.6			
		1	2.6	1.2		3.12			
		1	2.6	1.2		3.12			
		1	2.5	1.2		3			
		1	1.8	1.2		2.16			
		1	3	3.35		10.05			
		1	7.5	1.2		9			
		1	3.5	2		7			
						50.05	sq.m	34.00	1701.7
	item no-1, Page-192								
8	Labour for Chipping of concrete surface before taking up Plastering work.	1	3.35		3.00	10.05			
		2	1.20		3.00	7.20			
		2	1.80		3.00	10.80			
		2	1.20		3.00	7.20			
		2	2.25		3.00	13.50			
						48.75	sq.m	21.00	1023.75
	item no-10 ,page-91, 3rd corrigenda								
10	(a) M.S or W.I Ornametal grill of approved design joints contiluously welded with M.S, W.I flats and bars of Windows, railing etc. Fitted and fixed with necessary screws and lugs in ground floor.(Add extra @ 1% for each addl. Floor upto 4th floor and @ 1.25% for each addl. floors above 4th floor) (i) Grill weighing above 10kg per sq.m and up to 16Kg./sq.mtr.								

		1	1.2		2.1	2.52			
		1	1.5		1.2	1.8			
						4.32			
						0.52	Qntl	9,888	5125.94
Item no-01 Page 49, 3rd corrigenda									
11	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/ staging where necessary (ground floor). [Excluding cost of chipping over concrete surface] (i) with 1:6 cement mortar (b)15 mm Thick Plaster								
		1	3.00		3.60	10.80			
		1	2.00		3.60	7.20			
		1	3.00		3.00	9.00			
		1	2.00		3.00	6.00			
		1	2.00		2.40	4.80			
		1	3.00		2.40	7.20			
						45.00	Sqm	151.00	6795.00
item no-1, Page 50, 3rd corrigenda									
12	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/ staging where necessary (ground floor). [Excluding cost of chipping over concrete surface](i) with 1:4 cement mortar (c)10 mm Thick Plaster								
		1	6.50	1.20		7.80			
		1	2.25	1.20		2.70			
						10.50	Sqm	133.00	1396.50
item no-35, Page 65									
14	Supplying, fitting & fixing 1st quality Ceramic tiles in walls and floors to match with the existing work & 4 nos. of key stones (10mm) fixed with araldite at the back of each tile & finishing the joints with white cement mixed with colouring oxide if required to match the colour of tiles including roughening of concrete surface, if necessary or by synthetic adhesive & grout materials etc(B) Wall With Sand Cement Mortar (1:3) 15 mm thick & 2 mm thick cement slurry at back side of tiles using cement @ 2.91 Kg/Sq.m & joint filling using white cement slurry @ 0.20kg/Sq.m. (a) Area of each tile upto 0.09 Sq.m (ii) Other than Coloured decorative including white 2. Add extra for each addl. floor over the rate for item 35 & 36 of subhead A. (i) upto 4 th floor-Rs 5/ Sq.m								
	toilet ground floor, floor	4	2.2		2.1	18.48	Sqm.	704.00	13009.92
item no-10 page no-196									


15	Acrylic Distemper to interior wall, ceiling with a coat of solvent based interior grade acrylic primer (as per manufacturer's specification) including cleaning and smoothening of surface. Two Coats								
		1	3.00		3.20	9.60			
		1	2.00		8.50	17.00			
		1	6.35		3.00	19.05			
						45.65	Sqm	70.00	3195.5
		1	6.50	1.20		7.80			
		1	3.00	4.18		12.53			
		1	3.00	3.35		10.05			
		1	1.80	1.20		2.16			
		1	2.53	1.20		3.03			
		1	2.25	1.20		2.70			
						38.27	Sqm	70.00	2678.55
	item no-9 page no-196b								
16	Dry Distemparing to interior walls or ceiling including cleaning, washing, smoothening surface(b) Two coat								
		1	3.00		3.20	9.60			
		1	2.00		8.50	17.00			
		1	3.00		3.00	9.00			
		1	4.18		3.00	12.53			
						48.13	Sqm	49.00	2358.125
		1	6.50	1.20		7.80			
		1	3.00	4.18		12.53			
		1	3.00	3.35		10.05			
		1	1.80	1.20		2.16			
		1	2.53	1.20		3.03			
		1	2.25	1.20		2.70			
						38.27	Sqm	49.00	1874.985
	item no-7 page no-195b								
17	Applying Interior grade Acrylic Primer of approved quality and brand on plastered or concrete surface old or new surface to receive Distemper/ Acrylic emulsion paint including scraping and preparing the surface thoroughly, complete as per manufacturer's specification and as per direction of the EIC. (In Ground Floor)(b) Two Coats(i) Water based interior grade Acrylic Primer								
	out side wall	1	8.20		3.6	29.52			
		1	7.55		3.6	27.18			
	parapate wall	1	8.20		0.9	7.38			
		2	7.55		0.9	13.59			
						77.67	Sqm	44.20	3433.014
	item no-4 page no-201								
18	Applying Acrylic Emulsion Paint of approved make and brand on wall and ceiling including sand papering in intermediate coats including putty (to be done under specific instruction of Superintending Engineer) : (Two coats) (i) Standard Quality								
	out side wall	1	8.20		3.6	29.52			
		1	7.55		3.6	27.18			
	parapate wall	1	8.20		0.9	7.38			
		1	7.55		0.9	6.795			
						70.875	Sqm	62.00	4394.25


item no-1/ f page no-114									
19	Wood work in door and window frame fitted and fixed in position complete including a protective coat of painting at the contact surface of the frame excluding cost of concrete, Iron Butt Hinges and M.S clamps. (The quantum should be corrected upto three decimals). (f) Sishu, Gamar, Champ, Badam, Bhola, Mogra, Hallak	1	1.2	0.075	0.100	0.01	Cum.	76096.00	684.86
item no- (1) (iii) (b) page no-117									
20	Panel shutters of door and windows, as per design (each panel consisting of single plank without joint), including fitting and fixing the same in position but excluding the cost of hinge and other fittings. (iii) 35 mm thick shutters with 19mm thick panel (b) Sishu, Gamar, Champ, Badam, Bhola, Mogra, Hallak.	1	1.2	-	1.5	1.80			
						1.80	Sqm.	2948.00	5306.4
item no-4 /b, page no-140									
21	Supplying, fitting and fixing M.S clamps for door and window frame made of flat bent bar, end bifurcated with necessary screws etc. by cement (1:2:4) as per direction. (Cost of concrete will be paid separately) (b) 40mm X 6mm X 200mm length	8	-	-	-	8.00	Each	25.00	200
item no-5/ vii, page no-140									
22	Iron butt hinges.... (vii) 100mm. X 58mm. X 1.90mm.	8	-	-	-	8.00	Each	47.00	376
item no- 28/i Page 145									
23	Anodised aluminium Aldrop/ Sliding bolts approved quality manufactured from extruded section conforming to I.S specification (I.S 2681/66) and fitted and fixed complete. (i) 250 mm X 16 mm dia. Bolt	4	-	-	-	4.00	Each	233.00	932
item no-10/c Page 138									
24	Square or hexagonal square mesh netting made with 18 BWG galvanized wire fitted and fixed complete as per design including local sal wood battens of size 37.5mm X 25mm. C) 37.5mm mesh	4	1.8	-	1.4	10.1	Sqm	373.00	3759.84
item no-1/b, page no-200									
25	(b) Priming one coat on timber or plastered surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc. (i) For Door & Window	5	1.8	-	1.4	12.6	Sqm	38.00	478.80
item no-1/a, page no-200									
26	(a) Priming one coat on steel or metal surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc.	1	15.5	-	1.4	21.7	Sqm	29.00	629.3
item no- 2 A/a/ii page no-200									


27	(A) Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary. (a) On timber or plastered surface with super gloss (hi-gloss) (iv) two coats (white in shade) (i) For Door & Window	5	1.8	-	1.4	12.6	Sqm	78.00	982.8
Item no- 2 A/b/ii page no-200									
28	b) On steel or other metal surface	2	12.3	-	1.2	29.52			
		2	1	-	2.1	4.2			
						33.72		77.00	2596.44
Item no-41a, page no-69									
29	Supplying and laying true to line and level vitrified tiles of approved brand (size not less than 600 mm X 600 mm X 10mm thick) in floor, skirting etc. set in 20 mm sand cement mortar (1:4) and 2 mm thick cement slurry back side of tiles using cement @ 2.91Kg./sqM or using polymerised adhesive (6 mm thick layer applied directly over finished artificial stone floor/Mosaic etc without any backing course) laid after application slurry using 1.75 Kg of cement per sqM below mortar only, joints grouted with admixture of white cement and colouring pigment to match with colour of tiles / epoxy grout materials of approved make as directed and removal of wax coating of top surface of tiles with warm water and polishing the tiles using soft and dry cloth upto mirror finish complete including the cost of materials, labour and all other incidental charges complete true to the manufacturer's specification and direction of Engineer-in-Charge. (White cement, synthetic adhesive and grout material to be supplied by the contractor) (B) Light Colour								
	1st floor, room	1	3	4.2		12.60			
		1	3	3.1		9.30			
				Total		21.90		1276.00	27944.40
30	Logo & Marking (Non Schedule)	1					L.S	5000.00	5000.00
									103839.64

Cost of sanitary & plumbing work	10383.96
Cost of electrical work	10383.96
Total=	124607.57
Add 12% GST on Total amount	14952.91
Net Total=	139560.48
1% extra for labour welfare cess =	1395.60
Add 3% contingency =	4186.81
Grand Total:	145142.89
Say:	145143.00

Total RS. ONE lakh FourtyFive Thousand One Hundred Fourtythree only /-.


Sub-Assistant Engineer
NHM, South 24pgs.


Assistant Engineer
NHM, South 24pgs.


CMOH
South 24pgs.